BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2023-24/OW/WORK_INDENT1350

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/KPPP/13/2023-24, Date: 26-12-2023

Name of Work: Removal of silt & Repair and maintenance of footpath in new ward no. 11 Kodigehalli.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of PRADEEP SURAPARAJU	
				In Figures	In Words
1	2304.00	Supply of Unskilled (Heavy work),Unskilled (Light Work),Sweeper,Billover, Blue Printer, Chief Mazdoor, Labours The wages given below as per Department of Labour, GoK circular vide KAE 83 LMW 2022 dated 13-01-2023 wef 01-04-2023 are listed.for emergency works.	Day	619.27	Rupees Six Hundred Nineteen and Twenty Seven Paise Only
2	288.00	Supply of Skilled Mason or Brick layer Class-1 The wages given below as per Department of Labour, GoK circular vide KAE 83 LMW 2022 dated 13-01-2023 wef 01-04-2023 are listed. for emergency works.	Day	651.29	Rupees Six Hundred Fifty One and Twenty Nine Paise Only
3	810.00	Earth work excavation by manual means for drains, canals, waste weir, draft, approach channels, key trenches, foundation of Buildings & bridges and such simillar works in all kinds of soils, as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenaces required to complete the work. In all kinds of soils Depth upto 1.5 m	Cum	256.22	Rupees Two Hundred Fifty Six and Twenty Two Paise Only
4	630.00	Providing and laying 100mm thick pre-cast cover slabs over drains &Rain pit of width not exceeding 800 mm using M20 concrete reinforcedwith Micro Alloyed High carbon steel with 3mm - 3ply wired steel @ 2.00 kg/m2, slabs jointed in CM 1:3 proportion and nicely finished Includingproviding holes in the Cover slabs wherever necessary for easy drainageof surface water including of labour, materials, scaffolding, usage of machinery, curing, lead and lift charges etc, Complete.	Sqm	982.52	Rupees Nine Hundred Eighty Two and Fifty Two Paise Only
5	15.00	Supplying and fixing Pre cast reinforced concrete slab 23cm thick including cost of reinforcement as per design and drawing courses cost of all materials, labour complete as per specifications.	Sqm	4848.11	Rupees Four Thousand Eight Hundred Forty Eight and Eleven Paise Only
6	720.00	Providing and laying 60mm thick factory made cement concrete paverblock of approved shape and colour of M -30 grade made of C&D wasteby block making machine with vibratory compaction laid in requiredpattern and including over 50mm thick compacted bed of coarse sand,filling the joints with fine sand etc. all complete as per the direction ofEngineer-in-charge.	Sqm	847.00	Rupees Eight Hundred Forty Seven Only
7	810.00	Lead for disposal of earth shall be payable at Carriage rates (Lead & Lift) by mechanical means including loading and unloading up to 15kms.	Cum	281.63	Rupees Two Hundred Eighty One and Sixty Three Paise Only
8	37.50	Providing and constructing un-reinforced plain cement concrete pavement, thickness as per design, over a preparedsub base, with 43 grade cement or any other type as perClause 1501.2.2 M20 (Grade), coarse and fine aggregatesconforming to IS:383:2016, maximum size of coarseaggregate not exceeding 25 mm, mixed in a concrete mixerof not less than 0.2 cum capacity and appropriate weighbatcher using approved mix design, laid in approved fixedside formwork (steel channel, laying and fixing of 125 micronthick polythene film, wedges, steel plates including levellingthe formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate.	Cum	6748.47	Rupees Six Thousand Seven Hundred Forty Eight and Forty Seven Paise Only
9	1.50	Supply of Material component Bitumen (emulsion) Rapid Setting RS1* for all road works.	t	45738.00	Rupees Forty Five Thousand Seven Hundred Thirty Eight Only
10	180.00	Supply of Hydraulic Excavator of 0.9 m3 bucket on hire basis including operator, fuel and other incidental charges etc.,	hr	1429.31	Rupees One Thousand Four Hundred Twenty Nine and Thirty One Paise Only
11	384.00	Supply of Tipper-5.5 m3 on hire basis including operator, fuel and other incidental charges etc.,	hr	1494.96	Rupees One Thousand Four Hundred Ninety Four and Ninety Six Paise Only
12	75.00	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver/grader in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density	Cum	2709.34	Rupees Two Thousand Seven Hundred Nine and Thirty Four Paise Only

Signature of the Contractor

Executive Engineer

Name of Work: Removal of silt & Repair and maintenance of footpath in new ward no. 11 Kodigehalli.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of PRADEEP SURAPARAJU	
				In Figures	In Words
13	25.00	Supply of Material component M-Sand - Fine for all road works.	Cum	1562.72	Rupees One Thousand Five Hundred Sixty Two and Seventy Two Paise Only
14	25.00	Supply of Material component Granular Aggregates of 12mm downsize for all road works.	Cum	1411.31	Rupees One Thousand Four Hundred Eleven and Thirty One Paise Only
15	25.00	Supply of Material component Granular Aggregates of 40mm downsize for all road works.	Cum	1259.91	Rupees One Thousand Two Hundred Fifty Nine and Ninety One Paise Only
16	130.00	Supply of Material component Cement (OPC/PPC/PSC) for all road works.	Bag	310.21	Rupees Three Hundred Ten and Twenty One Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
Bruhat Bengaluru Mahanagara Palike